Statement showing outlay on works undertaken from Local Funds General from July to the end of December 1896.

	Name of Work.	Outlay from July to the end of December 1896.		
		Rs.	a	p.
1.	Constructing a mantapam at Srinivaspur in the Channarayapatna taluk ..	164	4	0
2.	Constructing a katte at Srinivaspur in the Channarayapatna taluk ..	246	0	6
3.	Improving the drinking water katte at Somanathanahalli	288	9	6
4.	Sinking a well at Savantanahalli, Arsikere taluk	143	2	0
5.	Establishment charges	43	0	0
	Total ..	885	0	0

B. G. KRISHNAIENGAR, *President.*

SHIMOGA DIVISION.

Dated 8th April 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga division, up to 30th April 1897, for constructing Bridges on Anantapur-Tirthahalli road (1. Bridge over Nowturhalla, 2. Bridge over Kushavati River, 3. Bridge over Sunkadahalli).

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1900.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing Bridges on Anantapur-Tirthahalli road" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Description of Work.	*Unit of work.*		*Rate per unit.*
Excavation	C. yds.	2,624	
Do clearing under-vents and approaches in front for water-way and for discharge down stream in rear ..	L. S.		
Tracing bank, &c.	L. S.		
Diversion of channel	L. S.		
Stone in surki mortar	C. ft.	28,420	
Stone in mortar	Do	56,245	
Arch-work stone in mortar ring pins	Do	1,089	
Do do sheeting	Do	4,864	
Centrings	No.	8	
Cornicing and copings	C. ft.	2,060	
Pointing with mortar	Sqr.	228·69	
Guard stones	No.	12	
Earth-filling approaches	C. yds.	12,736	
Turfing	Sqr.	725·80	
Gravelling	C. yds.	396	
Baling	L. S.		
Rough stone work	C. yds.	158	
Drainage pipes	Each.	32	

C. M. ANANDATIRTHA RAO, *Offg. Exec. Engr.*